

LEGEND

- Survey Station
- 26.43 — Level (cross indicates position unless arrowed)
- Kerb
- Drop Kerb
- Change of Surface
- Top / Bottom — Banking
- Hedge / Bush Canopy
- Gate
- Wall
- Fence
- Foul Drainage With dia. in mm
- Storm Drainage
- OH — Overhead Electricity Line
- UG — Underground Electricity Line
- OH — Overhead Telephone Line
- UG — Underground Telephone Line
- 0.4/8.0 12m — Tree with trunk(dia.)/ Ave spread(.dia.) Height if specified
- Sapling

ABBREVIATIONS (Where applicable)

GENERAL

- AV. Air Valve
- BB. Belisha Beacon
- BG. Box Gully
- BL. Bollard
- BP. Boundary Post
- BS. Bus Stop
- CD. Cable Duct
- CL. Cover Level
- CM. Cable Marker
- CPS. Concrete Paving Slabs
- DP. Down Pipe
- ECB. Electricity Control Box
- ECP. Electricity Cable Pit
- EJB. Electricity Cable Junction Box
- EP. Electricity Pole
- ERP. Earthing Point
- FB. Flower Bed
- FH. Fire Hydrant
- FIG. Feeds into Ground
- FP. Footpath
- G. Gully
- GP. Gate Post
- GV. Gas Valve
- H. Hydrant
- IC. Inspection Cover
- IL. Invert Level
- KO. Kerb Outlet
- LP. Lamp Post
- MH. Manhole
- MKR. Marker
- NB. Notice Board
- NFI. No Further Information
- NSIF. Not Surveyed - Information From
- P. Post
- PM. Parking Meter
- PRV. Pressure Reducing Valve
- RE. Rodding Eye
- RG. Road Gully
- RS. Road Sign
- RWP. Rain Water Pipe
- SC. Stop Cock
- SP. Signpost
- SV. Sluice Valve
- T. Tree
- TCB. Telephone Call Box
- THL. Threshold Level
- TIC. Telephone Inspection Cover
- TJB. Telephone Junction Box
- TL. Traffic Light
- TP. Telephone Pole
- UTL. Unable to Lift
- VP. Vent Pipe
- WL. Water Level
- WM. Water Meter
- WV. Water Valve

FENCES AND WALLS

- BKW. Brick Wall
- BLW. Block Wall
- BW. Post & Barbed Wire Fence
- CB. Close Boarded Fence
- CI. Corrugated Iron Fence
- CP. Chestnut Paling Fence
- CW. Concrete Wall
- DSW. Dry Stone Wall
- IR. Iron Railing Fence
- OB. Open Boarded Fence
- PC. Post & Chain Fence
- PCL. Post & Chain Link Fence
- PF. Panel Fence
- PR. Post & Rail Fence
- PW. Post & Wire Fence
- PWM. Post & Wire Mesh Fence
- RW. Retaining Wall
- SF. Security Fence
- STW. Stone Wall
- SW. Sheep Wire Fence

OTHER ABBREVIATIONS USED ON THIS SURVEY

NOTES

SURVEY TIED INTO NATIONAL GRID OSTN15 AND OSGM15 DATUM FOR HEIGHT USING GPS EQUIPMENT UTILIZING THE TRIMBLE VRS NOW SYSTEM FOR REAL TIME KINEMATIC (RTK) CORRECTIONS NATIONAL GRID SCALE FACTOR HAS NOT BEEN APPLIED TO THE SURVEY UNLESS SPECIFIED

DRAINAGE AND SERVICE INFORMATION SHOWN ON THIS SURVEY HAS BEEN OBTAINED BY VISUAL INSPECTION ONLY. ALTHOUGH ALL POSSIBLE CARE HAS BEEN TAKEN TO ENSURE THAT DETAILS SHOWN ARE CORRECT, WE ARE UNABLE TO ACCEPT ANY RESPONSIBILITY FOR COSTS ARISING OUT OF ANY ERRORS OR OMISSIONS.

COPYRIGHT: THIS DRAWING MAY NOT BE REPRODUCED IN ANY FORM WHATSOEVER WITHOUT THE CONSENT OF CJ SURVEYS LTD.

SURVEY STATION SCHEDULE

STN	EASTINGS	NORTHINGS	LEVEL	REMARKS
101	531717.596	282484.029	−0.620	TEMP NAIL
102	531752.916	282473.455	−0.276	MAG NAIL IN GRAVEL
103	531776.080	282464.704	−0.344	MAG NAIL IN GRAVEL
104	531771.016	282441.805	−0.290	MAG NAIL IN ASPHALT
105	531736.507	282433.957	−0.769	TEMP NAIL

C J SURVEYS LTD
LAND | BUILDING | ENGINEERING
PROFESSIONAL MEASURED SURVEYS
Tel: 01638 581031 Mobile: 07845 775645
Web: www.cjsurveys.co.uk E.mail: mail@cjsurveys.co.uk

CLIENT MRS ROBINSON C/O PARTNERS IN PLANNING & ARCHITECTURE

DATE	DRAWN	SHEET SIZE	SCALE
MAY 2021	CJ	A1	1:200

PROJECT TOPOGRAPHIC SURVEY
CHERRY LODGE, PUDDOCK ROAD, WARBOYS

DRAWING NO. 05721/T1