PLANT DETAILS	SPECIES NAME (LATIN)	APPROX SIZE OF PLANTS WHEN SUPPLIED / PLANTED	SPACING BETWEEN PLANTS (DENSITY)	NUMBER OF PLANTS PER SPECIES	CULTIVATION AND MAINTENANCE	GROWS TO
LAVENDER HIDCOTE	LAVENDULA ANGUSTIFOLIA HIDCOTE	9CM POT	0.75m	11	FIRST YEAR WATER REGULARLY AND TRIM IN APRIL	1.0m
WALKERS LOW	NEPETA RACEMOSA	2 LITRE POT	0.5m	6	BARK MULCHING AND TRIM AFTER FLOWERING	0.5m
MISS JESSOPS UPRIGHT	ROSMARINUS OFFICINALIS	2 LITRE POT	0.5m	2	LOCATE IN FULL SUN AND WELL DRAINED SOIL	1.0m
ROSEMARY	SALVIA ROSMARINUS	2 LITRE POT	0.5m	7	LOCATE IN FULL SUN AND WELL DRAINED SOIL	1.0m
FOXGLOVE	DIGITALIS	9CM POT	1.0m	6	LOCATE IN SHADE AND PRUNE AFTER FLOWERING	2.0m
SAGE	SALVIA OFFICINALIS	9CM POT	0.5m	7	LOCATE IN SUN AND PRUNE AFTER FLOWERING	0.5m
THYME	THYMUS VULGARIS	9CM POT	0.5m	8	CUT BACK AFTER FLOWERING	0.5m
MINT	MENTHE ARVENSIS	9CM POT	0.5m	8	WATER WELL AND DIVIDE IF EXCESSIVE SPREAD	1.0m
EUPHORBIA	EUPHORBIA CHARACIAS	2 LITRE POT	1.0m	4	GOOD DRAINAGE AND PRUNE FLOWERS IN AUTUMN	1.0m
LARKSPUR	DELPHINIUM	9CM POT	0.75m	4	STAKE WELL IN AUTUMN CUT DOWN TO GROUND LEVEL	1.5m
ALLIUM MILLENIUM	ALLIUM	2 LITRE POT	0.5m	2	GOOD DRAINAGE AND CUT BACK IN AUTUMN	0.5m
RED ROBIN	PHOTENIA FRASERI	2 LITRE POT	1.0m	16	GENEORUS MULCH AND PRUNE WELL LATE SUMMER	4.0m
CHERRY LAUREL	PRUNUS LAUROCERASUS	2 LITRE POT	1.0m	25	MULCH WELL AND STURDY GROWTH	4.0m
WILD CHERRY	PRUNUS AVIUM	9 LITRE	2.5m	4	PLANT AUTUMN STAKE FIRMLY LOW NITRATE FERTILISER	10.0m


SALVIA ROSMARINUS 'ROSEMARY'


THYMUS VULGARIS 'THYME'


MENTHA ARVENSIS 'MINT'


SALVIA OFFICINALIS 'SAGE'


TIVERTON PINK STONE


SANDSTONE PAVING AUTUMN GOLD


PRUNUS AVIUM 'CHERRY' TREE


LAVENDULA ANGUSTIFOLIA HIDCOTE 'LAVENDER HIDCOTE'


LARKSPUR 'DELPHINIUM'


BARK CHIPPINGS


TBS MYSTIQUE BRICKS


NEPETA RACEMOSA 'WALKERS LOW'


DIGITALIS 'FOXGLOVE'


EUPHORBIA CHARACIAS 'EUPHORBIA'


ROSMARINUS OFFICINALIS 'MISS JESSOPS UPRIGHT'


ALLIUM 'MILLENIUM'


PRUNUS LAUROCERASUS 'LAUREL' HEDGE



HARD AND SOFT LANDSCAPING PLAN
1:200 @ A1

NEW ROAD CROSSOVERS TO INCLUDE COATED MACADAM WEARING COURSE AND BASECOURSE OVER COMPACTED GRANULAR SUB-BASE, ALL TO BS 4987-1 AND -2. INSTALLATION TO INCLUDE PRECAST CONCRETE KERBS TO PERIMETER BY COUNCIL APPROVED CONTRACTOR AND ALL TO LOCAL HIGHWAY AUTHORITY SPECIFCATION

LANDSCAPE SPECIFICATION

GROUND PREPARATION

CLEAR ALL AREAS TO BE PLANTED OF RUBBISH, PLANT MATERIAL, STONES, ETC PRIOR TO EXCAVATION. EXCAVATE SHRUB PITS TO 500mm DEEP AND GRASS AREAS TO 300mm DEEP, FORKING THE BASE OF EXCAVATED AREAS TO ALLOW FOR DRAINAGE. EXCAVATE WHEN GROUND IS NOT WATERLOGGED. CHECK LOCATION OF ALL SERVICES BEFORE EXCAVATING. BACK FILL WITH TOPSOIL INCORPORATING PLANT COMPOST TO ALL PLANTING AREAS. IMPORTED TOPSOIL SHALL BE BS 3882: 2007.

PLANTING

THE PLANTING SEASON IS 1ST OCTOBER TO THE 31ST MARCH, HOWEVER CONTAINERISED STOCK CAN BE PLANTED OUTSIDE OF THIS SEASON IF WATERED DAILY. PLANTING SHALL NOT BE CARRIED OUT DURING PERIODS OF FROST, DROUGHT, FROZEN OR WATERLOGGED GROUND. ALL PLANTS SHALL BE SET OUT EVENLY OVER THE AREAS DETAILED ON THIS PLAN TO THE DENSITY SHOWN. ALL PLANTS SHALL BE UPRIGHT TO GROUND LEVEL AND EVENLY SPACED, LEAVING ROOM FOR GROWTH. IMMEDIATELY FOLLOWING PLANTING, ALL PLANTS SHALL BE WATERED IN TO FIELD CAPACITY. PLANTS TO BE FIRMED AND WATERED, REMOVING ANY DEAD OR DAMAGED BRANCHES AFTER PLANTING.

AMENITY GRASS SPECIFICATION

THE OWNER SHALL BE RESPONSIBLE FOR MAINTAINING THE AREA OF AMENITY LAWN. AREAS OF NEWLY TURFED GRASS TO BE CUT ONCE THE GRASS HAS REACHED 50mm IN HEIGHT. TURFED GRASS TO BE CUT AT LEAST 12 TIMES DURING THE INITIAL GROWING SEASON. ALL CUTTING OPERATION SHOULD BE CARRIED OUT IN SUITABLY DRY WEATHER CONDITIONS. ANY FAILED AREAS OF GRASS SHOULD BE RE-SEEDED AT THE CORRECT SEASON, USING THE ORIGINAL SPECIFIED SEED MIX. ANY INGRESS OF PERNICIOUS PERENNIAL WEEDS SHOULD BE HAND PULLED. NO SELECTIVE HERBICIDE SHOULD BE USED UNTIL THE GRASS IS FULLY ESTABLISHED.

ONCE ESTABLISHED FOR TWELVE MONTHS, GRASS TO BE CUT A MINIMUM OF 16 TIMES DURING EACH GROWING SEASON (GENERALLY BETWEEN MARCH AND OCTOBER). THE HEIGHT OF GRASS SHALL NOT EXCEED 75mm BEFORE CUTTING, TOPPED TO A HEIGHT OF 25-50mm.

THE LAWN SHOULD BE TREATED WITH AN APPROVED SELECTIVE HERBICIDE, AT THE RECOMMENDED RATE OF APPLICATION ON AN ANNUAL BASIS IN MAY OF EACH YEAR (SECOND YEAR ONWARDS), TO CONTROL BROAD-LEAVED WEEDS.

IF GRASS GROWTH IS POOR AND/OR TO ALLEVIATE SIGNS OF WEAR AND TEAR IT WILL BE NECESSARY TO APPLY A SPRING AND/OR AUTUMN FERTILISER, WHICH SHOULD BE APPLIED AT THE MANUFACTURERS RECOMMENDED RATES, TO ENCOURAGE VIGOUR.


PHOTINIA X FRASERI 'RED ROBIN'


MARSHALLS HARVEST DRIVESETT TEGULAR BLOCK PAVING

B	09-08-24	PLANTING SCHEDULE UPDATED
A	01-07-24	CLIENT AMENDMENTS

REVISIONS

COOK & COOK
2 WATER LANE
OAKINGTON
CAMBRIDGE
CB24 3AL
Tel : 01223 234849
Email : info@cookandcook.co.uk

Project
STONELY HOUSE
37 - 41 MAIN ROAD
STONELY, ST NEOTS PE19 5EH

For Tom Salkield

Drawing
PROPOSED HARD AND SOFT LANDSCAPING

Date	Scale
June 2024	1:200

Drawn by	Drawing no	Revision
AC	S667-DC-01	B
Checked by	File ref	
-		