SCHEDULE OF WORK

Site 5 - All Saints Church, St Ives, Cambridgeshire

Surveyed By: Alex Turner
Surveyed: 01/10/2024
Managed By: Alex Turner

Tree No	Tag No.	Species	Work required	Priority
T086	**618b**	Sycamore	Reduce crown on north aspect to establish a 2 metre clearance from church wall.	**3**
T088	**618d**	White Willow	Crown lift to 2.5 metres over hard surfacing.	**3**
T089	**618e**	White Willow	Crown lift to 2.5 metres over hard surfacing.	**3**
T091	**619**	European Lime	Reduce crown on western aspect to establish a 2 metre clearance from church wall. Crown lift on east aspect to establish a 1.5 metre clearance from adjacent structure. Remove Epicormic growth and Ivy from stem to reinspect for basal pathogens.	**3**
T092	**620**	European Lime	Remove Epicormic growth and Ivy from stem to reinspect for basal pathogens.	**3**
T093	**622**	European Lime	Remove Epicormic growth from stem to reinspect for basal pathogens.	**3**
T095	**624**	Holm Oak	Undertake cobra bracing maintenance.	**3**
T096	**625**	European Lime	Remove Epicormic growth and Ivy from stem to reinspect for basal pathogens.	**3**
T097	**626**	European Lime	Remove Epicormic growth from stem to reinspect for basal pathogens.	**3**
T098	**627**	European Lime	Remove Epicormic growth and Ivy from stem to reinspect for basal pathogens.	**3**
T099	**628**	European Lime	Remove Epicormic growth from stem to reinspect for basal pathogens.	**3**
T100	**629**	European Lime	Remove Epicormic growth from stem to reinspect for basal pathogens.	**3**
T101	**630**	European Lime	Remove Epicormic growth from stem to reinspect for basal pathogens.	**3**
T102	**631**	European Lime	Remove Epicormic growth from stem to reinspect for basal pathogens.	**3**
T103	**632**	European Lime	Remove Epicormic growth from stem to reinspect for basal pathogens.	**3**
T104	**633**	European Lime	Remove Epicormic growth from stem to reinspect for basal pathogens.	**3**
T105	**634**	European Lime	Remove Epicormic growth from stem to reinspect for basal pathogens.	**3**
T106	**635**	European Lime	Remove Epicormic growth from stem to reinspect for basal pathogens.	**3**
T107	**636**	European Lime	Remove Epicormic growth and Ivy from stem to reinspect for basal pathogens.	**3**
T108	**911**	European Lime	Remove Epicormic growth and Ivy from stem to reinspect for basal pathogens.	**3**