

Pond @934m2
20no. of each plant

Submerged -
Myriophyllum spiatum, Callitriche stagnalis ,Potamogeton crispus

Emergent -
Sparganium erectum, Ranunculus lingua, Potamogeton natans, Ranunculus aquatillis

Marginal Plants -
Myositis scorpioides, Mentha aquatica, Veronica anagallis-aquatica, Caltha palustris, Ranunculus flammula

Raised Planters
1. Steel planters L6000 x w1400 x h600 Ral tbc
2. Steel planters L6000 x w600 x h600 Ral tbc

822no. Cornus sanguinea / H 60-80cm / Br / @40cm cnt
924no. Prunus laurocerasus 'Mount Vernon' / Br @even cnt as shown
136no. Ceanothus thyrsiflorus repens / 3ltr / @ even cnt
160no. Hebe 'Green Globe' / 3ltr / 30cm cnt
48no. Euonymus japonicus 'Jean Hugues' / 2ltr / 40cm cnt
50no. Lavender 'Hidcote' Hedge / 2ltr /40cm cnt
70no. Viburnium tinus price / 2ltr / 40cm cnt
60no. Carex Ice Dance / 2ltr / even cnt

1446no. Mixed native hedge / Br / h 60-90cm / @4 per mtr / staggered double row, 38cm between rows, 45cm between plants
60% Crataegus monogyna / 10% Prunus padus
20% Acer campestre / 10% Carpinus betulus / 10% Ligustrum vulgare

Grass/Meadow Mix Sowing rate @ suppliers recommendation
2941m2 Naturescape N10 Woodland
2589m2 Naturescape N6 Clay Soil mix
400m2 Naturescape NL4 Hardwearing Lawn

Supporting documents

181	Spirotech Oakwood Planters	P01	
181	Spirotech Oakwood Tree Plan	TP01	r07
181	Spirotech Oakwood Landscape Maintenance		
181	Spirotech Oakwood Soft Landscaping Schedule		
181	Spirotech Oakwood Tree Pit Section		
181	Spirotech Oakwood Hardlandscaping Plan		

0 5 25 50

DO NOT SCALE OF THIS DRAWING USE ONLY DIMENSIONS SHOWN ALL DIMENSIONS TO BE CHECKED ON SITE IF IN DOUBT ASK

1. All planting beds to be weeded by hand prior to any work commencing.
2. All arising removed to tip.
3. All areas shall be kept weed free
4. All planting areas to be stone picked prior to commencement of planting with stone and other inorganic items larger than 20mm removed to tip
5. No residual herbicide to be used on planting areas as at any time
6. No ground works to be carried out while temperature is below 0 degrees or when ground is waterlogged
7. Planting area to be cultivated with a layer of soil improver together with bonemeal applied at 4ozsq yard or equivalent
8. All container grown plants to be planted within two days of arrival. If this is not possible, plants to be temporarily stored upright in a sheltered position away from drying winds and frost pockets with all plants being kept well irrigated
9. Container grown plants to be well watered prior to planting
10. All plants to be removed from pots and firmed in just below the finished soil height
11. All plants to be kept well irrigated after planting until the project is signed off by designer/client
12. All rootball trees to be planted within two days of arrival. Where this is not possible, plants to temporarily stored upright in a sheltered position away from drying winds and frost pockets with all plants being kept well irrigated during times of storage
13. No flora is to be planted whilst ground is frozen or when ground is waterlogged or excessively wet
14. Rootballed trees to be planted in a planting hole dug deep enough to accommodate the rootball. Tree to be placed into the planting hole complete with wire netting cut and peeled away from the top of the rootball prior to backlling the planting hole. Planting hole to be backfilled and soil firmed to finish height covering the top of rootball @50mm and of the surronding soil level
15. All areas to be mulched with woodchip grade 5-40mm to a 50mm depth, unless otherwise stated
16. Tree Pit Accessories - Perforated watering pipe to be supplied and fixed to each tree size appropriate to be fitted in accordance to the manufacturers instructions
17. Tree planting in these areas will need a tree pit for each tree to provide a planting hole x2 diameter of the rootball
18. Tree staking all standard trees with double short stakes, feathered trees with low single stake. Stakes to be rst grade pressure impregnated round timber with chamfered tops. Position stake close to tree on windward side and drive vertically at least 300mm into bottom of pit before planting.

Backlling: consolidate material around stake.
Height of stakes: cut to approximately one third of the tree height above ground level. Ties: Hessian. Tying: secure tree rmly but not rigidly to stake with at least 2 ties within 25mm of top of stake.
Tree locations may be relocated due to services/easements
Soil and Trees
Stockpiling of soil shall be avoided whenever possible to minimise loss of physical quality, diusion of oxygen and biological activity.
Tree rooting depth shall normally be 900mm. This will comprise of both topsoil and subsoil, the depth of topsoil spread shall not normally exceed 300mm. Suitable (loosened) subsoil shall provide the remainder of the minimum rooting depth.
Tree planting pit minimum soil volume to be no less than 9m3
Implementation
Planting and Ecology works will be carried out in the next available planting season after completion of the construction works

client	Spirotech	date	Dec 2023
project	Oakwood Sawtry	project no.	181 (111)
drawing	Shrub, Hedge, Meadow	drawing no.	SHM 01
scale	A1@ 1:500	rev	09

Landscape Architecture and Garden Design
t. 01733 393 010 w.otislandscapeassociates otis roberts