0 5 10 15 20 25
metres

Native Hedge Planting Mix
27 No. A ca 14%
27 No. C be 14%
27 No. C san 14%
27 No. C av 14%
27 No. F x 14%
29 No. M sy 15%
29 No. P pad 15%

Existing Leylandii hedge in this location to be removed

North Facing - Raingarden Mix
140 No. ALL SPH 5%
140 No. AST SCO 5%
140 No. AST SWH 5%
140 No. CAL FOE 5%
489 No. LUZ MAR 17.5%
140 No. PER SUP 5%
140 No. ELP ROB 5%
280 No. GER ALB 10%
140 No. HEU SPI 5%
280 No. IRI PSE 10%
140 No. DES GOL 5%
140 No. CAR SUP 5%
70 No. ROS WIN 2.5%

South Facing - Raingarden Mix
125 No. ALL SPH 5%
125 No. AST SCO 5%
125 No. AST CAR 5%
125 No. AST ALB 5%
249 No. BER OVE 10%
187 No. CAL FOE 7.5%
125 No. CAL SPE 5%
374 No. DES GOL 15%
374 No. GER ROZ 15%
187 No. MIS LIG 7.5%
125 No. PER SUP 5%
125 No. RUD GOL 5%
125 No. VER BON 5%

South Facing - Raingarden Mix
8 No. ALL SPH 5%
8 No. AST SCO 5%
8 No. AST CAR 5%
8 No. AST ALB 5%
16 No. BER OVE 10%
12 No. CAL FOE 7.5%
8 No. CAL SPE 5%
24 No. DES GOL 15%
24 No. GER ROZ 15%
12 No. MIS LIG 7.5%
8 No. PER SUP 5%
8 No. RUD GOL 5%
8 No. VER BON 5%

North Facing - Ornamental Planting Mix
12 No. A re 11%
12 No. Av 11%
12 No. BO 11%
12 No. DRA 11%
12 No. D f-m 11%
12 No. H o 11%
12 No. Lg 11%
12 No. P se 11%
14 No. Sc 12%

North Facing - Ornamental Planting Mix
19 No. A re 11%
19 No. Av 11%
19 No. BO 11%
19 No. DRA 11%
19 No. D f-m 11%
19 No. H o 11%
19 No. Lg 11%
19 No. P se 11%
21 No. Sc 12%

North Facing - Ornamental Planting Mix
23 No. A re 11%
23 No. Av 11%
23 No. BO 11%
23 No. DRA 11%
23 No. D f-m 11%
23 No. H o 11%
23 No. Lg 11%
23 No. P se 11%
25 No. Sc 12%

West Facing - Herbaceous Planting Mix
8 No. A m 'P' 8%
8 No. C x a 'K F' 8%
8 No. H a 8%
8 No. He 'M B' 8%
8 No. Ja 'Hella' 8%
8 No. K 'B' 8%
9 No. M ol 9%
9 No. M ca 9%
9 No. N t 9%
9 No. R f s 'G' 9%
8 No. V b 8%
8 No. V v 'A' 8%

West Facing - Herbaceous Planting Mix
1 No. A m 'P' 8%
1 No. C x a 'K F' 8%
1 No. H a 8%
1 No. He 'M B' 8%
1 No. He 'R T' 8%
1 No. K 'B' 8%
2 No. M ol 9%
2 No. M ca 9%
1 No. N t 9%
2 No. R f s 'G' 9%
1 No. V b 8%
1 No. V v 'A' 8%

West Facing - Herbaceous Planting Mix
38 No. A m 'P' 8%
38 No. C x a 'K F' 8%
38 No. H a 8%
38 No. He 'M B' 8%
38 No. He 'R T' 8%
38 No. K 'B' 8%
43 No. M ol 9%
43 No. M ca 9%
43 No. N t 9%
43 No. R f s 'G' 9%
38 No. V b 8%
38 No. V v 'A' 8%

West Facing - Herbaceous Planting Mix
25 No. A m 'P' 8%
25 No. C x a 'K F' 8%
25 No. H a 8%
25 No. He 'M B' 8%
25 No. He 'R T' 8%
25 No. K 'B' 8%
28 No. M ol 9%
28 No. M ca 9%
28 No. N t 9%
25 No. R f s 'G' 9%
25 No. V b 8%
25 No. V v 'A' 8%

1 No. CAR FAS
1 No. FAG DAW
1 No. QUE KOS
1 No. CAR FAS
1 No. FAG DAW

Native Hedge Planting Mix
32 No. A ca 14%
32 No. C be 14%
32 No. C sa 14%
32 No. C av 14%
32 No. F x 14%
34 No. M sy 15%
34 No. P pad 15%

Existing Soft Landscape

Existing Soft Landscape

Existing Soft Landscape

Planting Schedule

Trees

Number	Abbreviation	Species	Height	Girth
7	CAR FAS	Carpinus betulus 'Fastigiata'	400-450cm	16-18cm
2	FAG DAW	Fagus sylvatica 'Dawyck'	400-450cm	16-18cm
1	QUE KOS	Quercus robur 'Fastigiata Koster'	400-450cm	16-18cm

North Facing - Ornamental Planting Mix

Number	Abbreviation	Species	Pot Size	Specification	Density	Percentage Contribution
54	A re	Ajuga reptans	2L	Full Pot- C	9/m²	11%
54	Av	Alchemilla vulgaris	50cc min.	Plug. Established Root 2-3 Months min. - British Native-origin: C	9/m²	11%
54	BO	Betonica 'Overtop'	2L	Full Pot- C	9/m²	11%
54	DRA	Dryopteris affinis	2L	Full Pot- C	9/m²	11%
54	D f-m	Cyrtomium falcimas	2L-2.5L	Full Pot- C	9/m²	11%
54	H o	Helleborus orientalis	2L	Full Pot- C	9/m²	11%
54	Lg	Liboritia grandiflora	2L	Full Pot- C	9/m²	11%
54	P se	Polystichum setiferum	2-2L	Full Pot- C	9/m²	11%
59	Sc	Sesleria caerulea	2L	Full Pot- C	9/m²	12%

Total: 483

West Facing - Herbaceous Planting Mix

Number	Abbreviation	Species	Pot Size	Specification	Density	Percentage Contribution
11	A m 'P'	Achillea millefolium 'Paprika'	2L	Full Pot - C	9/m²	8%
11	C x a 'K F'	Calamagrostis x acutiflora 'Karl Foerster'	2L	Full Pot - C	9/m²	8%
11	H a	Hebe allicans	2L	Bushy. 3 brks: C	9/m²	8%
11	He 'M B'	Helenium 'Moerheim Beauty'	2L	Full Pot - C	9/m²	8%
11	He 'R T'	Helenium 'Ruby Tuesday'	2L	Full Pot - C	9/m²	8%
11	K 'B'	Knautia 'Bronsteine'	2L	Full Pot - C	9/m²	8%
11	M ol	Miscanthus sinensis	2L	Full Pot - C	9/m²	8%
11	M ca	Molinia caerulea	2L	Full Pot - Sept to April planting: British Native-origin: C	9/m²	9%
11	N t	Nassella trichotoma	2L	Full Pot- C	9/m²	9%
11	R f s 'G'	Rudbeckia fulgida sullivantii 'Goldsturm'	2L	Full Pot- C	9/m²	9%
11	V b	Verbena bonariensis	2L	Full Pot- C	9/m²	8%
11	V v 'A'	Veronicastrum virginicum 'Album'	2L	Full Pot- C	9/m²	8%

Total: 412

Native Hedge Planting Mix

Number	Abbreviation	Species	Specification	Density	Percentage Contribution
59	A ca	Acer campestre	1+1	Transplant - seed raised: B	0.33Ctr Double Staggered at 0.33m offset	14%
59	C be	Carpinus betulus	1+1	Transplant - seed raised: B	0.33Ctr Double Staggered at 0.33m offset	14%
59	C san	Cornus sanguinea	1+1	Transplant - seed raised: Provenance UK Area 403 - B	0.33Ctr Double Staggered at 0.33m offset	14%
59	C av	Corylus avellana	1+2	Transplant - seed raised: Branched: 4 brks: B	0.33Ctr Double Staggered at 0.33m offset	14%
59	F x	Fagus sylvatica	1+2	Transplant - seed raised: B	0.33Ctr Double Staggered at 0.33m offset	14%
63	M sy	Malus sylvestris	1+2	Transplant - seed raised: B	0.33Ctr Double Staggered at 0.33m offset	15%
63	P pad	Prunus padus	1+1	Transplant - seed raised: B	0.33Ctr Double Staggered at 0.33m offset	15%

Total: 421

North Facing - Raingarden Mix

Number	Abbreviation	Species	Specification	Density	Percentage Contribution
280	AJU REP	Ajuga reptans	Full Pot- C	9/m²	10%
140	ASP SCO	Asplenium scolopendrium	Full Pot- C	9/m²	5%
140	CAR ALB	Carex pendula 'Moonraker' Syn White'	Full Pot- C	9/m²	5%
140	CAL EVI	Calamagrostis x acutiflora 'Karl Foerster'	Full Pot- C	9/m²	5%
420	CAR EVE	Carex oshimensis 'Everest'	Full Pot- C	9/m²	15%
140	DRY AFF	Dryopteris affinis	Full Pot- C	9/m²	5%
140	EUP ROB	Euphorbia amygdaloides robbiae	Full Pot- C	9/m²	5%
280	GER ALB	Geranium phaeum 'Album'	Full Pot- C	9/m²	10%
140	HEU SPI	Heuchera 'Green Spice'	Full Pot- C	9/m²	5%
140	IRI PSE	Iris pseudacorus	Full Pot- C	9/m²	5%
489	LUZ MAR	Luzula sylvatica 'Marginata'	Full Pot- C	9/m²	17.5%
140	PER SUP	Persicaria bistorta 'Superba'	Full Pot- C	9/m²	5%
70	ROS WIN	Rosenia pinnata 'Chocolate Wing'	Full Pot- C	9/m²	2.5%

Total: 2799

This drawing is not to be scaled. All dimensions to be checked on site.
Discrepancies, ambiguities and / or omissions between this drawing and information given elsewhere must be reported immediately to head office for clarification before proceeding.

Legend

- Site Boundary
- Works happening outside the redline

Softworks

- North Facing - Ornamental Planting Mix
- West Facing - Herbaceous Planting Mix
- North Facing - Rain Garden Mix
- South Facing - Rain Garden Mix
- Double Staggered Row Native Hedge Planting
- Existing Hedgerow to be Coppiced and Gaps Filled with Species Listed Below (Quantites to be Determined on Site)
  - Acer campestre 80-100cm
  - Carpinus betulus 80-100cm
  - Corylus Avellana 80-100cm
  - Malus sylvestris 80-100cm
- Proposed Tree
- Existing Tree Retained
- Existing Tree Removed

Revised Site Plan	S2	P06	CLO	CHU	13/10/26
Revised Site Plan	S2	P05	CLO	CHU	08/10/26
Revised Site Plan	S2	P04	LHY	CHU	10/09/26
Revised Site Plan	S2	P03	CLO	CHU	01/09/26
Revised	S2	P02	CLO	CHU	28/01/26
First Issue	S2	P01	CLO	CHU	01/12/25
Revision	POI	Rev	Author	Agreed	Date

newcastle:
Door 19, Teapots 1 & 2, Hoults Yard, Walker Road, Newcastle, NE6 2HL t: +44 (0)191 281 3775
edinburgh:
91 George Street, Edinburgh EH2 3ES t: +44 (0)131 241 0309

oobe

w: www.oobe.co.uk e: info@oobe.co.uk

Client: Alliance Leasure
Project: Huntingdon Leisure Centre

Title: Proposed Planting Plan

Dwg. No. 6283-OOB-ZZ-00-D-L-0001
Revision P06
Scale 1:500 @A0
Date January 2026

PLANNING