

Shrub Planting
Plants should be planted during the planting season (mid-November to mid-March) Plants will be positioned as per this drawing and planting schedule. All planting works must be carried out in accordance with the relevant current British standards. Plant handling at the nursery, during transit up to delivery, should be in accordance with "Plant Handling" booklet published by the Committee for Plant Supply and Establishment (CPSE) and the contractor shall comply with clauses 3 and 4 of the above booklet. This can be obtained from the Horticultural Trades Association telephone 01734 303132. This refers to the receipt, unloading and temporary storage of plants. Plants shall be first class examples of their species or variety. They shall be free from all pests and diseases with good fibrous root systems and materially undamaged (refer to relevant sections of BS3936 parts 1-10 Specification of Nursery Stock). All planting is to be in general compliance with BS4428 : 1989 Code of Practice for General Landscape Operations (excluding hard surfaces).

Preparation of Planting Beds
Topsoil must be moist but not waterlogged. Planting should not take place if soil is frozen or snow covered. Compacted topsoil will be broken up with large stones and undesirable material removed. The beds will be mulched with a 100mm minimum deep layer of dark matured wood chip mulch. The mulch shall contain less than 5% wood and shall be pest, disease and weed free. The final mulch surface is to be left in a tidy, raked condition.

New Hedging
Plant between October and February. Hedging plants are to be 60-80cm high bare root healthy and vigorous transplants. These plants will be planted through a 500mm wide weed control membrane secured with approved pegs at 1m centres down both sides. The plants will be placed in a double staggered row 400mm apart with 4 plants per square metre. All transplants will be protected with a 400mm high plastic spiral rabbit guard supported by a 750mm stake cane. The hedge is to be maintained for a period of 5 years following planting. The contractor must ensure adequate watering and fertilising is carried out to assure good establishment and that dead, diseased or damaged plants are replaced annually as required.

Lawn Turf
Excavate and cart away existing vegetation and topsoil to depth of 150mm. All earth clods and stones larger than 40-50mm should be removed. Lay imported topsoil to depth of 150mm. The surface will then be raked level and lightly firmed but should not be over-compacted. Turf should be healthy and vigorous and laid to form a close-knit sward. Use mix including fescues, perennial rye grass and smooth stalk meadow grass. All precautions must be taken to avoid drying out and turf should be laid within 18 hrs of delivery and watered immediately. Turf should not be stacked to a height of more than 1m. Avoid turfing when ground is frozen or waterlogged.

		Shady Beds - Planted at 3/m2				
Plant Name	**Pot Size**	**A (2m2)**	**B (3m2)**	**C (2m2)**	**D (3.2m2)**	**Total**
Anemanthele lessoniana	2 litre	3	3	2		8
Bergenia 'Ballawley'	2 litre			2	2	4
Pachysandra terminalis	2 litre			2	2	4
Prunus laurocerasus 'Otto Luyken'	3 litre		3			3
Sarcococca confusa	2 litre	3			3	6
Skimmia japonica	2 litre		3		3	6
Total		**6**	**9**	**6**	**10**	**31**

2.5m2 Sunny Shrub Mix - Planted at 3/m2		
Plant Name	**Pot Size**	**No.**
Stipa tenuissima	2 litre	3
Lavandula angustifolia 'Hidcote'	3 litre	3
Stachys byzantina	2 litre	2

Hedging - Planted in 2 staggered rows at 4/m2			
Plant Name	**Height**	**Specification**	**No.**
Carpinus Betulus	60-80-cm	Bare root	208

New 1.8m timber closeboard fence

Existing timber fence to remain

Lawn Turf

Paving - Marshalls Fairstone Sawn Versuro 855x570x22mm 'Caramel Cream' in stretcher bond pattern

Block Paving - Marshalls Savanna Linear 200x50x60mm 'Pennant Grey' in stretcher bond pattern

0 1 2 3 4 5m

SAF Landscape Design
8 Hamerton Road, Alconbury Weston, Cambridgeshire, PE28 4JD
www.saflandscapedesign.com

Client:	Berrys
Project:	Land off Allerton Garth, Alwalton
Title:	Landscape Proposals
Date:	02.07.25
Scale:	1:100 @ A1
DWG No:	B-AGA-LP01
Rev:	A

All dimensions to be checked by contractor on site

N