Planting Mixes 0303

Area Name	Qty	Botanical Name	Pot size	Scheduled Size	Rate/Spacing	Specification	Percentage of mix %
Shrub bed	0						
	72	Acer campestre		80-100cm	2 Plants/sq m	1+2; Transplant - seed raised	25
	72	Crataegus monogyna		80-100cm	2 Plants/sq m	1+2; Transplant - seed raised	25
	14	Hedera helix	2L	40-60cm	2 Plants/sq m	Several shoots; 3 brks	5
	29	Ilex aquifolium	3L	60-80cm	2 Plants/sq m	Leader with laterals	10
	58	Prunus spinosa		80-100cm	2 Plants/sq m	1+2; Transplant - seed raised; branched; 3 brks	20
	14	Rosa canina		60-80cm	2 Plants/sq m	1+1; Transplant - seed raised; branched; 3 brks	5
	29	Viburnum opulus		60-80cm	2 Plants/sq m	1+2; Transplant - seed raised; branched; 3 brks	10

Trees					
Name	Qty	Pot Size	Height	Girth	Specification
Prunus avium	3	RB	400-450cm	16-18cm	3x; EHS; clear stem min. 200cm
Tilia cordata	2	RB	400-450cm	16-18cm	3x; EHS; clear stem min. 200cm

0.3d
0.4d
1-Tilia cordata
1-Tilia cordata
1-Prunus avium
1-Prunus avium
1-Prunus avium
72-Acer campestre
72-Crataegus monogyna
14-Hedera helix
29-Ilex aquifolium
58-Prunus spinosa
14-Rosa canina
29-Viburnum opulus

Note:
Planting shown outside of site planning boundary, but within client ownership to align with BNG calculations

Planning boundary

Neutral grassland
Germinal Seeds WFG4 Neutral Soils mix or similar neutral grassland mix.
Seed mix to be sown at a rate of 5g/m^2.
Mix to be sown in two equal sowings at right angles to each other and diagonally to main axis

Proposed shrub planting.
Refer to schedule for plant species, sizes, numbers and densities.
Planting to be in species groups of 3-5 with adjustements of upto 300mm in any direction to avoid straight lines.
Refer to note about protection

Proposed tree planting.
Refer to schedule of plant species and size.
Refer to note about staking

All trees, shrubs and hedgrows are to be planted in accordance with the implementation and maintenance guidelines.
No tree, shrub or hedgerow species, size or location should be altered without prior approval from the Landscape Architect.
All Extra Heavy Standard (EHS) trees are to be double staked. Refer to detail MONKS-WWA-ZZ-ZZ-D-L-0501 D02.
All transplant planting to be staked with a 600mm high plastic spiral shelter secured with a stake/cane and tie as per manufacturers reccomendations
All planting beds to have 50mm depth bark mulch.
Before trees are planted the Landscape Contractor shall to the best of their ability ascertain the location of drains and any site easements from the site manager and if necessary make minor adjustments to the tree positions to ensure that they are planted with the appropriate offsets from these services.

No.	Date	Appr	Revision Notes
S3 P 03	14/02/25	TJ	Layout updated
S3 P 02	06/02/25	LH	Sheet title amended
S3 P 01	29/01/25	KL	First issue

Note: All Dimensions must be checked on site and not scaled from this drawing.
All cross references are to the latest revision of the relevant drawing or specification being referenced

Scale/North Point: 1:200 — 0 10 20 m
Drawing size: ISO A1
Drawn: MJB
Checked: KL
Uniclass: PM_40_40_34
Date: 29/01/2025

Client: Cambridgeshire Constabulary
Contractor: Willmott Dixon
Job Title: Monks Wood Police Training Centre
Issue: STAGE 3

© Copyright
wynne-williams associates
landscape architects & arboricultural consultants
web: w-wa.co.uk tel: 01376 573050

Drawing Title: Landscape Planting Plan Refurbished Building

Drg: MONKS-WWA-RB-ZZ-D-L-0303 | Status: S3 | Rev: P03