Schedule of works – Church Yard, located in Great Gransden Conservation Area

T1, Common lime, Remove basal/trunk epicormic shoots and deadwood of 40mm diameter or greater throughout crown.

> Arboricultural Tree Condition Report 2026 states: 'Dense epicormic shoots prevent close inspection of base to south and west.' 'Occasional scattered small diameter dead wood throughout crown.'

T2, Common lime, Remove basal/trunk epicormic shoots and deadwood of 40mm diameter or greater throughout crown.

> Arboricultural Tree Condition Report 2026 states: 'Dense epicormic shoots prevent close inspection of base to north, south and west.' 'Scattered moderate deadwood throughout crown.'

T8, English oak, Raise crown over adjacent house to clear by 2m. Reduce lowest substantial limbs overhanging neighbouring property by approximately 3m and remove crossing branches.

> Arboricultural Tree Condition Report 2026 states: 'Southern overhangs neighbouring dwelling; peripheral canopy is brushing against roof.'

T10, Black Locust, Reduce stem with crack at base by half current height.

> Arboricultural Tree Condition Report 2026 states: 'Deep crack propagating downwards from union of principal crown stems to north at 2m; stems appear to be subsiding away from main trunk, union opening.'

T19, Wild cherry, Lift over path to 3m. Cut back from adjacent house to clear by 3m.

> Arboricultural Tree Condition Report 2026 states: 'Overhangs path and bench.' 'Eastern canopy overhangs neighbouring dwelling; peripheral canopy is brushing against roof.'