
CIVILS
INTERCEPT DUCT RUNNING PAST BUILDING ON ROYAL OAK PASSAGE
LAY NEW DUCT TEE AT APPROX GR;523714,271890 AND 4M D56 TO
NEW POKE OUT AT REAR OF BUILDING


RUN UP WALL AND DRILL THROUGH TO
BUILDING NEXT TO WINDOW


RUN AT HIGH LEVEL IN NEW TRUNKING TO COMMS CUPBOARD
DRILL IN TO CUPBOARD AND TERMINATE IN TO NEW SOF3A IN COMMS CAB



RUN AT HIGH LEVEL IN NEW TRUNKING TO COMMS CUPBOARD
DRILL IN TO CUPBOARD AND TERMINATE IN TO NEW SOF3A IN COMMS CAB
SPLICE F1 TO 5M PIGTAIL AND FIT NEW NTE
SPACE AND POWER AVAILABLE