DD86

Install 670.2_300 sign x 2

Install 670.2_300 sign x 2

Install 670.2_300 sign x 2

Install 670.2_300 sign x 2

Cut back trees for visibility from both directions. Approx 37m x 2m

Install Pudsey Offsey 76mm sign post. 4m. Grey
Install 674 sign
Install 675_30 sign

Install 1065_20 marking
Install 1065_30 marking

Cut back trees for visibility from both directions. Approx 37m x 2m

Install offset sign bracket
Install 674 sign
Install 675_30 sign

35.28m

36.70m

BOCKING CLOSE

BLOOMFIELD DRIVE

CHRISTIE DRIVE

Woodland Lodge

N

Notes

THIS DRAWING IS TO BE READ IN CONJUNCTION WITH THE PROJECT PRE-CONSTRUCTION INFORMATION

ALL STREET FURNITURE TO BE OFFSET FROM THE EDGE OF CARRIAGEWAY BY A MINIMUM OF 450MM UNLESS OTHERWISE STATED.

ALL TRAFFIC SIGNS ARE TO CONFORM TO 'THE TRAFFIC SIGNS REGULATIONS & GENERAL DIRECTIONS 2016' (TSRGD) & ANY SUBSEQUENT AMENDMENTS.

ALL NEW POST POSITIONS TO BE MARKED ON SITE BY CCC ENGINEER AND REPRESENTATIVE FROM MILESTONE

ALL POSTS TO BE GALVANISED STEEL

ALL SIGNS TO BE ORIENTATED AS SHOWN

ALL DIMENSIONS GIVEN IN THIS DRAWING ARE IN METRES UNLESS SPECIFICALLY STATED OTHERWISE.

ALL SIGNAGE MATERIALS ARE TO BE CLASS RA2 (BS EN 12899-1:2007) REFLECTORISED, EXCEPT BLACK OR BROWN

THERE ARE SEVERAL BURIED SERVICES IN THE VICINITY OF THE PROPOSED WORKS. IT IS RECOMMENDED THE CONTRACTOR CARRIES OUT PRELIMINARY NON-INTRUSIVE INVESTIGATIONS PRIOR TO ANY EXCAVATIONS BEING UNDERTAKEN. TO LOCATE THE EXISITNG SERVICES THROUGH THE USE OF CAT SCANNING EQUIPMENT. IT IS ALSO RECOMMENDED THAT EXCAVATIONS ARE CARRIED OUT BY HAND WHERE POSSIBLE WITH THE USE OF INSULATED SHOVELS.

ELECTRICAL DISCONNECTIONS, SOLAR AND MAINS - ARE TO BE CARRIED OUT BY TRAINED AND COMPETENT PERSONNEL ONLY

ALL ROAD MARKINGS ARE TO CONFORM TO 'THE TRAFFIC SIGNS REGULATIONS & GENERAL DIRECTIONS 2016' (TSRGD) & ANY SUBSEQUENT AMENDMENTS

Key:

- SP — Proposed sign post
- SP — Existing sign post
- Existing Dropped Kerb
- Existing Raised Features
- 20 — Install 1065 Roundel Marking. 20,30 or 40 as displayed
- 20 — Existing 1065 marking
- Existing Street Lighting
- SP — Remove Sign Post
- DO — Disconnection/Removal of VAS/WIG WAG
- Refresh lining. White or yellow as shown
- 20 — 1065 Roundel Marking to have numeral changed. 20,30 or 40 as displayed

Date	Rev	Description
27.09.2024		FOR CONSTRUCTION

Cambridgeshire County Council

Project
TCF
20MPH Zone
Huntingdon

Title
Detailed Design
Signs, Posts and Markings

Scale	Drawn	Checked	Date
1/750@A3	DN	JL	SEP 24

Based upon Ordnance Survey material with the permission of the controller of Her Majesty's Stationery Office. Unauthorised reproduction infringes copyright and may lead to prosecution. © Crown Copyright and database rights (2020) Ordnance Survey **100023205**

Drawing number
30CPX31339_HUN_DD86

Rev