

CLASS Q

Materials Schedule – Rev A

Site Address:
High Street
Stilton

Prepared for: Oakwood Homes

Facing brickwork.
Ashington Red Multi with white cement.
www.wienerberger.co.uk/content/dam/wienerberger/united-kingdom/marketing/documents-magazines/product-data-sheets/brick/new-versions/UK_MKT_DOC_BRI_24240070_Ashington_Red_Multi.pdf
(A sample panel has been constructed on site for inspection if required).



Pitched roof.
Russell Galloway Thin Leading Edge interlocking roof tile in Anthracite.
https://www.russellrooftiles.com/product/natural-range/galloway/



Windows.
UPVC casement & sash windows as per the below and as elevated on the approved drawings, colour Classic Cream (RAL 9001), set back 50mm from the external masonry face in the reveals.
Plots 1, 4 & 5 have flush casement windows.
Plots 2 & 3 have sash windows.





Front door.
Woodgrain composite, colour black (RAL 9005), set back 50mm from the external masonry face in the reveals.



Bi-fold doors.
PPC aluminium, colour Classic Cream (RAL 9001), set back 50mm from the external masonry face in the reveals.



Garage doors.
Ribbed steel up & over doors, colour black (RAL 9005), set back 50mm from the external masonry face in the reveals.



Soffit, fascia & rainwater goods.
UPVC soffits, fascias & rainwater goods, colour black (RAL 9005).

